





Artist's Concept only
Specifications are approximate and subject to change at the builder's discretion. E. & O. E.

48 Melbourne Street, Hamilton Two Storey 1788 SF
2 available lots 25' x 140' Infill property

SILVESTRI
HOMES
silvestrihomes.ca



MAIN FLOOR PLAN



SECOND FLOOR PLAN

48 Melbourne Street, Hamilton Two Storey 1788 SF
 2 available lots 25' x 140' Infill property

Artist's Concept only
 All measurements are expressed in Imperial units.
 Specifications are approximate and subject to change at the builder's discretion. E. & O. E.

SILVESTRI
HOMES
 silvestrihomes.ca

SILVESTRI HOMES

STANDARD FEATURES & FINISHES **48 / 50 Melbourne - Hamilton**

EXTERIOR FEATURES

1. All exterior designs, colours and house sittings to be architecturally controlled by Silvestri Homes. All homes are presited.
2. Brick/siding front elevations as per plans. All stucco sides and back.
3. Decorative municipal address plaque for all homes.
4. Maintenance free aluminum soffits, fascia, eavestrough and down pipes.
5. Upgraded Architectural style shingles.
6. Fully sodded lots. Pre-cast concrete steps with slabs leading to driveway.
7. Paved driveway.
8. Maintenance free vinyl casement windows with multipoint lock and fold away handles, colour selection by builder's sample. Note: basement windows are white sliders.
9. Steel insulated garage door. Note: locking hardware will only be installed on request.
10. One exterior hose bib in rear yard and one in garage (location to be determined by Silvestri Homes).
11. All porches and garages reinforced with 15M rebar spaced at 16" on center. All garage and basement floors are saw cut.
12. Garages to be fully drywalled, taped, gas proofed, 1 coat of drywall compound and lightly sanded.
13. Garage exterior walls are insulated with R-12. No vapour barrier.

ELECTRICAL FEATURES

14. 100 amp overhead electrical service with circuit breaker panel.
15. 220 V outlets provided for stove and dryer.
16. Electrical outlet provided for future garage door opener.
17. Two exterior outlets, 1 in rear yard and 1 in front on ground faulted line controlled by 1 GFI outlet.
18. All bathrooms on a ground faulted line controlled by 1 GFI outlet
19. ARC fault breakers provided as required by code.
20. Builder to install as standard 12" 3 clip domes throughout. Vanities to have chrome strip bars. No chandeliers will be installed. Builder will install customer supplied light fixtures at an additional cost.
21. White decors switches and plugs.
22. One electrical outlet in great room provided for wall mounted TV.
23. R.I. wiring for future dishwasher. No breaker will be provided. Purchasers must call a licensed electrician.

24. Smoke detector, strobe and carbon monoxide detector(3 in 1) in all bedrooms and all floors, interconnected with back up batteries.

25. Location of hydro meter to be determined by Silvestri Homes and or electrical company.

26. Exterior wall light provided at garden door.

27. Microwave electrical outlet on its own dedicated circuit for over the range microwave.

FLOORING FEATURES

28. Upgraded imported 12"x24" porcelain floor tiles from builder's standard selection for all bathrooms and laundry areas. Shower and tub walls to be selected from wall tile selections.

29. Upgraded 40 oz carpet with upgraded 3/8" high density chip pad on entire second floor, less tiled areas. Selection from builder's samples.

30. 7 1/2" wide luxury vinyl planks on main floor less tiled areas.

31. All sub flooring is 3/4" thick aspenite, nailed, glued, screwed and joints sanded.

BATHROOMS, PLUMBING & LAUNDRY FEATURES

32. White plumbing fixtures throughout.

33. Comfort height elongated toilets.

34. Chrome single lever faucets for all bathrooms.

35. Mirrors, towel racks, soap dishes and toilet paper holders are not provided.

36. Custom shower door and jamb surrounds for ensuite.

37. Shut off valves for all plumbing fixtures.

38. 5' x 32" acrylic soaker tub in main bath.

39. 36" high vanities for extra comfort. Choice of semi maple or semi oak from standard selection. Soft close doors and drawers

40. Post formed laminate countertops from standard selections.

41. Upgraded quiet soft air bathroom exhaust fans including laundry room.

42. Venting sleeve for dryer.

43. Plastic laundry tub in laundry room with drain and water connections for washer.

KITCHEN CABINETRY FEATURES

44. Selection from stain semi maple or semi oak standard selections, group 1.

45. Top drawer construction.

46. Crown moulding and light valance trim.

47. 1 set of pots and pan drawers.

48. Full depth fridge upper cabinet and fridge gables.

49. Soft close doors and drawers.

50. Double ledge back stainless steel sink with single lever pullout chrome faucet.

(continued)

51. Post formed laminate countertops.

52. 12" deep upper cabinets.

53. Provisions for over the range microwave.

54. Cabinet opening to accommodate future dishwasher (plumbing rough in and electrical rough in provided).

55. Bulkheads above kitchen cabinets if required. 36" upper cabinets are standard.

INTERIOR FEATURES

56. Main floor to second floor stairs to be carpet grade with oak stringers. Stairs from main floor to basement are paint grade utility stairs. Stain colour to be selected from Min Wax Stain.

57. Oak handrails and square contemporary spindles.

58. 2-3/4" colonial style casing in finger joint pine along with 5-1/2" colonial style baseboards in finger joint pine. All trim painted white.

59. 9' main floor ceiling height.

60. 8' second floor ceiling height.

61. 9' x 8' patio door off living room.

62. 2 panel smooth doors throughout. Includes entrance and garage man door.

63. Quality pewter hardware throughout Kwikset front door to have gripset

64. Rough in central vacuum (pipe dropped to basement).

65. Rough in CAT 5 and cable in every bedroom and 1 on main floor. Location TBD by Silvestri Homes unless specified by buyer. No activation by builder. Blank cover plates to be provided.

66. Upgraded smooth ceilings throughout.

67. Wire shelving in all closets. Shoe rack to be provided for main floor closets.

68. Resilient channel on 2nd floor ceilings for a straighter ceiling and to maximize truss uplift.

69. All trim and doors to be painted white.

70. Choice of 2 interior paint colours for walls, in a flat finish.

QUALITY CONSTRUCTION FEATURES

71. 2"x6" exterior wall construction.

72. 16' engineered floor joist construction(over code). No beams in basement.

73. 3/4" thick aspenite sub floor.

74. 3/8" thick roof plywood sheeting.

75. All high walls constructed with 2x6 timberstrand studs to ensure a straighter wall and minimize shrinkage.

76. 8" poured concrete foundation wrapped with Delta MS waterproof membrane.

77. Sewer back flow preventer in all basements.

ENERGY SAVING FEATURES

78. Programmable thermostat.

79. Energy Star Efficiency windows.

80. R-22 exterior walls and R-31 in cathedral ceiling areas or no access ceiling areas.

81. R-60 blown in attic insulation.

82. R-31 2 lb polyurethane foam insulation over garage and living space bump outs.

83. All gaps around window openings to be foamed.

84. All main floor joist cavities are spray foamed with R-22 2 lb polyurethane.

85. Lennox Elite Series EL296 high efficiency two stage furnace (96% efficiency). Available 10 year parts warranty when you register appliance.

86. High efficiency 50 gallon HOT WATER TANK (RENTAL).

87. Furnace interconnected to ENERGY RECOVERY VENTILATOR (ERV).

88. Ducting sized for future air conditioner.

NOTE:

89. House layout may be reversed from brochure.

90. Risers to home may vary from brochure.

91. Some homes may have a step down from mudroom to accommodate less risers in garage.

92. Silvestri Homes reserves the right to make minor changes at their discretion.

93. Brochure is an artist concept.

PROMOTIONS

• Upgraded faucets throughout

• 5 1/4" baseboards

• All smooth ceilings

• 12" x 24" porcelain floor tiles

WARRANTY

Silvestri Homes is proud of our exemplary record with Tarian Warranty Corporation covering the following items:

1. The home is free from defects in workmanship and materials for one (1) year.

2. The home is free from defects in workmanship and materials on electrical, plumbing, heating delivery and distribution systems, exterior cladding, windows and doors, building envelope and basement remains free from water penetration for two (2) years.

3. The home is warranted against all major structural defects for seven (7) years.